

Pasadena Drainage Improvements Since July 2017

CIP #	Project Name	Description/Limits	Status	Funding Source	Cost (Estimate)
D039	Partnership Park Annex Drainage Improvements	30 acre foot detention and recreation facility adjacent to Partnership Park	Design	CDBG-DR (GLO)/Harris County/City	\$ 1,500,000.00
D042	Browning Subdivision Drainage Improvements	Alleviate area flooding between Red Bluff Rd and Center Street south of Spencer.	Drainage Evaluation	City (CO's)	\$ 1,400,000.00
D043	2018 Annual Drainage Improvements Project	Helen - Added 200' of 18" pipe to alleviate ponding - no drainage before Miami - South of Wallis, replaced large inlet box that was damaged Pansy - Turnberry to Colonial, cleaned ditch Wichita - Martha to Marlen, replaced 336' of tinhorn pipe with 24" reinforced concrete pipe (RCP) Lilac - Holly to Spencer, upsize in driveway pipes and excavated ditch Janus - Flagler to Olson, added 438' of 24" reinforced concrete pipe (RCP) - no drainage before W Thomas - Richey to Mobile, added 520' of 24" reinforced concrete pipe (RCP) - no drainage before Space Center - Gleneagles to France, added 225' of 18" reinforced concrete pipe (RCP) - no drainage before Preston - Replaced inlets from Fleming to Thomas	Complete	City (GF)	\$ 374,337.00
D044	Golden Acres Detention/Bliss Meadows Drainage	Two detention facilities developed in Spencer Village and Bliss Meadows	Design	CDBG-DR (GLO)/Harris County/City	\$ 1,100,000.00
D045	2019 Annual Drainage Improvements Project	Knob Hill - West of Center St, replaced pipe with larger size, 95' of 18" RCP and 356' of 24" RCP Crenshaw - Anthony Lane and BW8, added 750' of drainage ditch along eastbound lane St. Jude - Added 248' pf 18" RCP along the whole street Red Bluff Rd - Replaced inlets from Pasadena Blvd to Spencer Hwy Double Eagle - Crenshaw and Crystal Doves, added 318' of 12" RCP and inlets	Complete	City (GF)	\$ 372,015.00
D056	Armand Bayou Upper Reaches Project	Construction of long overflow flood channel between Red Bluff and Big Island Slough to alleviate flooding north of Fairmont Parkway.	Design	CDBG-DR (HC)/City (CO's)	\$ 8,300,000.00
D057	2020 Annual Drainage Improvements Project	Burke - Replaced inlets from Spencer to Cherrybrook Los Verdes - Watters to Palos Verdes, added 300' of 18" RCP and inlets - no drainage before Palos Verdes - Watters to Los Verdes, added 300' of 18" RCP and inlets - no drainage before	Construction	City (GF)	\$ 788,200.00
D058	Fairmont Parkway Drainage Imprpovements	Construction of a closed storm system from Burke to Preston	Design	PEDC	\$ 3,500,000.00
M018	Utility Development	Burke - Installed 700' of concrete ditch liner between Parkview and Brookshire Crenshaw - Installed 1,475' of concrete ditch liner between Burke and Parkland	Complete	PEDC	\$ 871,918.30
S001	Thomas Ave Paving & Drainage	Preston Rd to Burke Rd - Drainage was added during construction	Complete	CDBG (Comm Dev)	\$ 207,796.09
S045	Pansy Street Paving & Drainage Phase I	Spencer Hwy to Old Vista - Section was open ditch and has now been enclosed	Complete	City (CO's)	\$ 605,616.46
S047	Wafer Street Paving & Drainage Phase II	Southmore Ave to Harris Ave - Drainage will be added in certain sections and pipe will be upsized in some areas	Design	CDBG (Comm Dev)/City (CO's)	\$ 575,000.00
S048	Lafferty Street Paving & Drainage	Spencer Hwy to Fresa Rd - Drainage was added in certain sections and pipe was upsized in some areas	Construction	City (CO's)	\$ 834,021.62
S077	Pasadena Blvd Reconstruction	SH 225 to Harris Ave - Drainage was re-designed to increase capacity	Design	Harris County/PEDC	\$ 4,000,000.00
S101	Richey Street Reconstruction	SH 225 to Southmore Ave - Storm sewer pipes were upsized	Construction	Harris County/PEDC	\$ 3,725,362.15
S104	Wafer Street Paving & Drainage Phase I	Harris to Eagle - Drainage was added during construction	Construction	CDBG (Comm Dev)/City (CO's)	\$ 655,460.62
S107	Shaw Street Reconstruction	Carl St to McMasters Ave - Storm sewer pipes will be upsized	Contract Award	PEDC/City (CO's)	\$ 777,231.46
S109	Thomas Ave Paving & Drainage Phase II	Bearle St to Alastair - Drainage will be added during construction	Design	City (CO's)	\$ 275,000.00